

SECTION 013000 - ADMINISTRATIVE REQUIREMENTS

PART 1 - GENERAL

1.1 PROJECT MANAGEMENT AND COORDINATION

- A. Verify dimensions of existing site features shown on Drawings before laying out the Work.
- B. Coordinate construction to ensure efficient and orderly execution of each part of the Work.
- C. Progress meetings will be held at the jobsite every week to two weeks, as deemed necessary to review progress of the Work and facilitate Contractor's questions during construction. The schedule for these meetings will be as determined by the Architect and the selected Contractor. Each Subcontractor or other entity concerned with current progress, or involved with planning or coordination of future activities, shall attend.
 - 1. Architect will record minutes and distribute to Contractor, and Owner. Contractor shall distribute minutes to Subcontractors.

1.2 SUBMITTAL PROCEDURES

- A. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
 - 1. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
 - 2. Submit five copies of each submittal. Architect will return two copies.
 - 3. Architect will discard submittals received from sources other than Contractor.
- B. Place a permanent label or title block on each submittal for identification. Provide a space approximately 6 by 8 inches on label or beside title block to record Contractor's review and approval markings and action taken by Architect. Include the following information on the label:
 - 1. Project name.
 - 2. Date.
 - 3. Name and address of Contractor.
 - 4. Name and address of subcontractor or supplier.
 - 5. Number and title of appropriate Specification Section.
- C. Identify deviations from the Contract Documents on submittals.
- D. Contractor's Initial Construction Schedule Submittal Procedure: Submit two copies of schedule within seven days after date established for Commencement of the Work.

PART 2 - PRODUCTS

2.1 ACTION SUBMITTALS

- A. Product Data: Mark each copy to show applicable products and options. Include the following:
 - 1. Manufacturer's written recommendations, product specifications, and installation instructions.
 - 2. Wiring diagrams showing factory-installed wiring.
 - 3. Printed performance curves and operational range diagrams.
 - 4. Testing by recognized testing agency.
 - 5. Compliance with specified standards and requirements.
- B. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data. Submit on sheets at least 8-1/2 by 11 inches but no larger than 24 by 36 inches. Include the following:
 - 1. Dimensions and identification of products.
 - 2. Fabrication and installation drawings and roughing-in and setting diagrams.
 - 3. Wiring diagrams showing field-installed wiring.
 - 4. Notation of coordination requirements.
 - 5. Notation of dimensions established by field measurement.
- C. Samples: Submit Samples for review of kind, color, pattern, and texture and for a comparison of these characteristics between submittal and actual component as delivered and installed. Include name of manufacturer and product name on label.
 - 1. If variation is inherent in material or product, submit at least three sets of paired units that show variations.

2.2 INFORMATION SUBMITTALS

- A. Qualification Data: Include lists of completed projects with project names and addresses, names and addresses of architects and owners, and other information specified.
- B. Product Certificates: Prepare written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.

2.3 CONSTRUCTION SCHEDULE

- A. Gantt-Chart Schedule: Submit a comprehensive, fully developed, horizontal Gantt-chart-type schedule within 30 days of date established for commencement of the Work.
- B. Preparation: Indicate each significant construction activity separately. Identify first workday of each week with a continuous vertical line.

PART 3 - EXECUTION (Not Applicable)

3.1 SUBMITTAL REVIEW

- A. Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- B. Architect will review each action submittal, make marks to indicate corrections or modifications required, stamp and mark as appropriate to indicate action taken, and return copies less those retained.

3.2 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. Distribute copies of approved schedule to Owner, Architect, subcontractors, testing and inspecting agencies, and parties identified by Contractor with a need-to-know schedule responsibility. When revisions are made, distribute updated schedules to the same parties.
- B. Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule at each regularly scheduled progress meeting.
 - 1. As the Work progresses, indicate Actual Completion percentage for each activity.

END OF SECTION 013000